OFFICE OF THE CHIEF ELECTRICAL ENGINEER, BANGALORE.

Notification dated 5th November 1937.

A Gold Ring, engraved R. C., was found in the premises of the Government Middle School, Sivasamudram (Bluff), on 31st January 1937. The owner of the ring may claim it with proper evidence from the General Superintendent, Generating Station, Sivasamudram, on or before 31st December 1937, after which date the ring will be auctioned and the amount realised credited to Government.

Abstract Notification dated 5th November 1937.

The attention of the public is invited to Notification dated 5th November 1937, published on page 1878 of Part VI of the *Mysore Gazette*, dated 11th November 1937, calling for tenders for the purchase of lead scrap available at the C. P. S. Central Stores, Bangalore City.

A. C. MUNIRATNAM,
For *Chief Electrical Engineer.*

OFFICE OF THE SUPERINTENDING ENGINEER, ELECTRICAL DEPARTMENT, BANGALORE.

Notification dated 1st November 1937.

Notice is hereby given that sealed tenders will be received at the Office of the Superintending Engineer, Electrical Department, Bangalore, up to 2 P.M., on 27th November 1937, for constructing :

(1) Transformer Station, Office and Stores.
(2) Two units of Senior Operator and Main Line Inspector's Quarters.
(3) Three units of Double Block of Operator's Quarters.
(4) Eight blocks of Line Men's Quarters.
(5) Thirteen blocks of latrines at Davangere Town.

1. The tenders will be opened in public at 2 P.M. on 27th November 1937. The work should be completed within 6 months and the monthly progress should not be less than Rs. 10,000.

2. The quantities given are approximate and the plans, detailed estimates and the conditions may be seen at the Superintending Engineer's Office, Bangalore, on all working days during the office working hours.

3. Tenders should be submitted on printed forms which may be obtained from the Superintending Engineer. The tenders should be accompanied by a statement in the form given bleow showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 1,500 in cash or Government Promissory Notes, as earnest money and be superscribed " Tender for constructing electrical buildings at Davangere Town," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Electrical Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender. The Chief Electrical Engineer also reserves the right to accept or reject any portion of the tender.

6. Within 8 days of the award of the tender, the successful tenderer will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful tenderer will be posted on the Notice Board in the Superintending Engineer's Office, Electrical Department, in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The construction work should be started within a fortnight from the date of the notification of the acceptance.

10. Charges on account of scaffolding, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately but should be borne by the contractor.

11. Rates once tendered will not be enhanced on any account.

12. Rates for non-tendered and non-estimated items shall be as per schedule rates of the [illegible]artment or those fixed by the Superintending Engineer after working out data with not more [illegible]10 per cent for contractor's profit.

13. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Chief Electrical Engineer will be final and legally binding.

14. Specifications for works are those recognised by the Mysore Public Works Department and Marryot's specifications.

15. The contractor should be bound by the conditions of the schedule of contract of the Electrical Department.

Abstract estimate for the cost of constructing a combined building for Station, Office and Stores at Davangere.

Sl. No.	Items of work	Per	Rate	Quantity
			Rs. a. p.	
1	Earthwork excavation and filling in basement	C.yd.	0 3 0	100
2	Stone jelly in lime mortar concrete for foundation ..	C.ft.	0 4 0	798
3	Size stone in lime mortar for foundation and basement ..	,,	0 5 0	2,299
4	Burnt brick in lime mortar, superstructure	,,	0 4 6	3,181
5	Stone slabs 6″ thick, exposed parts 2 line dressed and set in lime mortar	S.ft.	0 8 0	183
6	Stone slabs 6″ thick roughly dressed and set in lime mortar	,,	0 6 0	228
7	Chunam plastering, two coats	Sqr.	3 4 0	62.88
8	Cement pointing with thread lines	,,	4 4 0	3.22
9	White and colour washing, two coats	,,	0 4 0	66.10
10	Flooring with 1st class Mangalore Tiles on 6″ lime concrete and cement painted	,,	40 0 0	11.82
11	Flooring with Cuddapah slabs 1½″ thick on 3″ lime concrete and cement pointed	,,	28 0 0	4.21
12	Teakwood doors panelled 1½″ thick with fixtures complete. (as per drawing)	S.ft.	1 12 0	126
13	Teakwood windows with glazed shutters 1¼″ thick and iron bars ¾″ dia. complete (as per drawing) ..	,,	2 0 0	175
14	Teakwood ventilators with glazed shutters 1″ thick with iron bars ¾″ dia. complete	,,	1 4 0	47
15	Providing and fixing R.C. jelly-work as per plan ..	,,	1 8 0	138
16	Teakwood partition with 3″×4″ scantlings for frames and 1″ thick planks, with tongue and groove joints with fittings complete including 2 coats of wood oiling (as per drawing)	,,	1 12 0	144
17	Providing and fixing rolled steel girders of Tata (tested) make including painting	Cwt.	15 0 0	57.29
18	Terrace filled with brick nogging in surki mortar complete with wedge R.C. joists complete (as per detailed drawing)	Sqr.	75 0 0	19.55
19	Brick in lime mortar parapet wall 9″ thick and 1′9″ high, with lime plaster, etc., complete as per design ..	R.ft.	1 0 0	273
20	Brick in lime mortar, cornice plain as per plan ..	,,	0 8 0	281
21	Cement concrete with centerings including plastering at bottom and sides complete	C.ft.	0 12 0	46
22	Boxing girders with brick in mortar and nice plastering	R.ft.	0 8 0	90
23	Burnt brick in lime mortar pillars 1⅛′×1⅛′×10′ with base and capitals as per design with bond slabs at intervals of 3 to 4 feet with lime plastering and white and colour washing, two coats, etc., complete ..	Each	10 0 0	No. 8
24	Providing and fixing rain water down pipes of 3″ square size, made of 22 B.W.G. plain gald iron sheet, fixed with necessary clamps, etc., including painting ..	R.ft.	0 6 0	204
25	Silver grey silicate painting, two coats	Sqr.	4 8 0	5.06
26	Providing store racks	L. S.	300 0 0	one item
27	Supplying and fixing 2″ G.I. pipe for flag staff in cement with necessary clamps	,,	5 0 0	,,
28	Providing and fixing slabs 4″ thick on 3″ lime concrete below rain water pipes	S.ft.	0 4 0	
29	Printing letters 6″×4″ with cement and painting ..	L. S.	8 0 0	one item
30	Providing openings with necessary lintels, etc., for incoming and outgoing lines	,,	100 0 0	,,

Constructing a Senior Operator's and Line Inspector's Quarters at Davangere.

Sl. No.	Items of work	Per	Rate	Quantity per block
			Rs. a. p.	
1	Earthwork excavation in ordinary and gravelly soil ..	C.yd.	0 3 0	75
2	Stone jelly concrete in mortar for foundation	C.ft.	0 4 0	600
3	Size stone in clay for foundation and basement including bond stones at every 6′ apart in each course ..	,,	0 3 6	1,664
4	Burnt brick in clay superstructure	,,	0 3 3	1,794
5	Brunt brick in lime mortar do	,,	0 4 6	912
6	Stone slabs 6″ thick roughly dressed and fixed in lime mortar	S.ft.	0 8 0	202
7	Stone slabs 3″ thick fixed over "I" beam, etc. ..	,,	0 5 0	28
8	Pointing with cement mortar	Sqr.	4 4 0	2.31
9	Plastering with lime mortar, 2 coats	,,	3 4 0	55.61
10	White and colour washing, 2 coats	,,	0 4 0	57.92
11	Plain cornice 9″ deep	R.ft.	0 6 0	103
12	Burnt brick in mortar 9″ thick parapet ordinary ..	,,	1 0 0	100
13	Flooring with 1″ cement concrete on a bed of 3″ lime concrete and ½″ cement plastering complete ..	Sqr.	20 0 0	10.07
14	Mangalore tiled roofing 1st class on T. W. reepers 2″×1″ including wood oiling to reepers	,,	33 0 0	11.56
15	Mangalore Ridge Tiles set in mortar and cement pointed..	R.ft.	0 8 0	73
16	Terrace filled in with brick nogging in surki mortar complete with wedge R.C. joists as per detailed drawing	Sqr.	75 0 0	5.74
17	Teakwood work with wood oiling complete	C.ft.	6 0 0	60.11
18	Plain teakwood eave boarding 9″×¾″	R.ft.	0 6 0	162
19	Teakwood doors with battened shutters 1″ thick frames 4″×3″ with fixtures complete as per drawing ..	S.ft.	1 4 0	183
20	T.W. windows with battened shutters 1″ thick with iron bars, etc., complete as per drawing	,,	1 12 0	110
21	T.W. Cup-boards with T.W. Shelves complete.. ..	,,	1 8 0	48
22	Expanded metal 3″×1½″ with ⅛″ strands with T.W. frames fixed complete with doorways, etc. ..	,,	0 12 0	111
23	R.S. girders (Tata's) tested including painting	Cwt.	15 0 0	4.31
24	Chocolate painting, two coats	Sqr.	3 8 0	10.36
25	Mangalore ventilating tiles fixed complete	Each	2 0 0	6
26	Constructing sinks	,,	5 0 0	2
27	Providing new stone mortar and pestle and fixing ..	,,	5 0 0	1
28	Chunam borders at roof ends	R.ft.	0 3 0	26
29	Rain water down pipes 3″ dia. of plain G.I. sheeting fixed complete including painting	,,	0 8 0	110
30	Constructing chimney in kitchen	L. S.	..	..
31	Levelling ground	L. S.	..	..

Constructing one Unit of Double Block of Operator's Quarters at Davangere.

Sl. No.	Items of work	Per	Rate	Quantity per block
			Rs. a. p.	
1	Earthwork excavation and filling in basement	C.yd.	0 3 0	74
2	Stone jelly in lime concrete for foundation	C.ft.	0 4 0	702
3	Size stone in clay for foundation and basement ..	,,	0 3 6	1,762
4	Burnt brick in clay	,,	0 3 3	3,338
5	Burnt brick in lime mortar superstructure	,,	0 4 6	859
6	Stone slabs 6″ thick roughly dressed and set in lime mortar	S.ft.	0 8 0	278

Sl. No.	Items of work	Per	Rate	Quantity per block
			Rs. a. p.	
7	Stone slabs 3″ thick set in lime over I beam in front, etc.	S.ft.	0 5 0	29
8	Chunam plastering 2 coats	Sqr.	3 4 0	73·0
9	Pointing with cement mortar	,,	4 4 0	3·12
10	White and colour washing 2 coats	,,	0 4 0	76·12
11	Plain cornice 9″ deep complete	R.ft.	0 6 0	73
12	Burnt brick in mortar parapet wall 9″ thick complete as per design	,,	1 0 0	70
13	Burnt brick in lime mortar parapet wall 9″ thick and 2′—9″ high complete	,,	1 0 0	15
14	Flooring with 1″ thick cement concrete on a bed of 3″ lime concrete and cement plastered ½″ thick on top ..	Sqr.	20 0 0	13·16
15	Roofing with 1st Class Mangalore Tiles on T.W. reepers	,,	33 0 0	13·16
16	Mangalore ridge tiles set in mortar and cement pointed ..	R.ft.	0 8 0	126
17	Terrace filled in with brick bogging in Surki mortar complete with wedge R.C. joists complete as per drawing	Sqr.	75 0 0	5·44
18	Teakwood work with wood oiling complete	C.ft.	6 0 0	60·11
19	Teakwood eave boarding plain 9″×¾″	R.ft.	0 6 0	192
20	Teakwood doors with battened shutters 1″ thick with iron bars ⅝″ dia., with fixtures, etc., complete with frames 3″×4″	S.ft.	1 12 0	188
21	Teakwood doors with battened shutters 1″ thick with fixtures complete with frames 4″×3″	S.ft.	1 4 0	241
22	T.W. Cup-board with T.W. Plank shelves complete ..	,,	1 8 0	96
23	Expanded metal 3″×1½″ of ⅛″ strands with T.W. frame work including door ways fixed complete	,,	0 12 0	119
24	Chocolate painting 2 coats	,,	3 8 0	14·57
25	Mangalore Ventilating tiles fixed complete	Each	2 0 0	8
26	Constructing sinks in bath room with outlet pipe ..	,,	5 0 0	2
27	Providing stone mortar and pestle	,,	5 0 0	2
28	Rain water down pipe 3″ dia. fixed complete including painting	R.ft.	0 8 0	65
29	Providing and fixing handas in bath room (Brass or copper)	Each	12 0 0	2
30	Rolled steel girders of Tata's (tested) make fixed complete including paint	Cwt.	15 0 0	4·34

Abstract estimate for constructing Line men's Quarters at Davangere.

Sl. No.	Items of work	Per	Rate	Quantity per block
			Rs. a. p.	
1	Earthwork excavation and filling in basement ..	C.yd.	0 3 0	33
2	Stone jelly in lime mortar concrete for foundation ..	C.ft.	0 4 0	287
3	Size stone in clay for foundations and basement ..	,,	0 3 6	911
4	Burnt brick in clay superstructure	,,	0 3 3	1,692
5	Stone slabs 6″ thick roughly dressed and fixed in mortar	S.ft.	0 8 0	195
6	Burnt bricks in lime mortar superstructure	C.ft.	0 4 6	513
7	Binding wall 6″×6″ of brick in lime mortar and chunam plastered	R.ft.	0 3 0	28
8	Chunam plastering, two coats	Sqr.	3 4 0	45.04
9	Painting with cement mortar and thread lines ..	,,	4 4 0	1.45
10	White and colour washing, two coats	,,	0 4 0	46.49
11	Roofing with I Class Mangalore Tiles on T.W. reepers including wood-oiling to reepers, etc., complete, ..	,,	33 0 0	14.43
12	Ridge tiles set in mortar and cement pointed complete ..	R.ft.	0 8 0	77
13	Ventilating tiles set in mortar and cement pointed complete	Each	2 0 0	16
14	Teak wood work wrought and put up complete with wood oiling two coats	C.ft.	6 0 0	52.48

Sl. No.	Items of work	Per	Rate	Quantity per block
			Rs. a. p.	
15	Doors with teakwood frames and teakwood battened shutters 1" thick with fittings, etc., complete	S.ft.	1 4 0	156
16	Windows with teakwood frames and teakwood battened shutters 1" thick with iron bars $\frac{5}{8}$" diameter and fittings and hinges, etc., complete	S.ft.	1 12 0	60
17	Chocolate painting two coats	Sqr.	3 8 0	4.62
18	Constructing sinks in bath rooms	Each	5 0 0	4
19	Providing and fixing stone mortar and pestle in	"	5 0 0	4
20	Flooring with 3" lime concrete and 1" cement concrete and $\frac{1}{2}$" thick cement plastering on top, etc., complete	Sqr.	20 0 0	7.58
21	Levelling ground facilitating drainage	L. S.	10 0 0	1 Item
22	Constructing parapet wall with brick in lime mortar 2' high, including Cuddappah slab on top with plastering in mortar, etc.	R.ft.	0 12 0	37
23	Providing expanded metal trellis work in front verandah including doors, etc., complete	S.ft.	0 12 0	241

Abstract estimate of the probable cost of constructing one Unit of Latrine for Quarters at Davangere.

Sl. No.	Items of work	Per	Rate	Quantity per block
			Rs. a. p.	
1	Earthwork excavation for foundation	C.yd.	0 3 0	4
2	Stone in mortar foundation and basement	C.ft.	0 5 0	130
3	Burnt brick in mortar superstructure	C.ft.	0 4 6	193
4	Chunam plastering, two coats	Sqrs.	3 4 0	4.91
5	Cement pointing with thread lines	"	4 4 0	0.56
6	White and colour washing, 2 coats	"	0 4 0	5.47
7	Cement plastering, $\frac{1}{2}$" thick	"	8 0 0	0.80
8	Tar washing, two coats	"	2 8 0	0.63
9	Flooring with 3" concrete 1" cement concrete and plaster $\frac{1}{2}$" thick in cement	"	20 0 0	0.38
10	Fixing outlets, constructing drains	L. S.	10 0 0	1 Item
11	Providing galvanised iron sheet tubs 12"×6" complete with tarring	Each	0 12 0	No. 6

L. A. H. WINCKLER,
Superintending Engineer.

OFFICE OF THE DISTRICT LOCK-UP OFFICER, CHIKMAGALUR.

Abstract Notification dated 9th November 1937.

Attention of the public is invited that sealed tenders for the supply of diet and other articles required for the District Lock-up, Chikmagalur, for the year 1938, will be received by the District Lock-up Officer, at his office at 9 A.M., on 3rd December 1937.

For further particulars please refer to Part VI, pages 1826-1827 of the *Mysore Gazette*, dated 4th November 1937.

V. SRINIVASA MUDALIAR,
Officer-in-charge.

OFFICE OF THE MANAGER, GOVERNMENT EXPERIMENTAL FARM, HIRIYUR.

Abstract Notification dated 6th November 1937.

The attention of the public is invited to the Notification dated 3rd November 1937, calling for ers for the execution of works in connection with sugarcane harvest at Babbur Farm, published age 1879, Part VI of the *Mysore Gazette*, dated 11th November 1937.
The last date for receiving tenders is 6th December 1937.

T. KRISHNASWAMY,
Farm Manager